

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 3

AMENDED REPORT ☐

APPLICATION FOR PERMIT TO DRILL						1. WELL NAME and NUMBER Dart 4-14-3-2WH					
2. TYPE OF WORK DRILL NEW WELL <input checked="" type="checkbox"/> REENTER P&A WELL <input type="checkbox"/> DEEPEN WELL <input type="checkbox"/>						3. FIELD OR WILDCAT UNDESIGNATED					
4. TYPE OF WELL Oil Well Coalbed Methane Well: NO						5. UNIT or COMMUNITIZATION AGREEMENT NAME					
6. NAME OF OPERATOR NEWFIELD PRODUCTION COMPANY						7. OPERATOR PHONE 435 646-4825					
8. ADDRESS OF OPERATOR Rt 3 Box 3630 , Myton, UT, 84052						9. OPERATOR E-MAIL mcrozier@newfield.com					
10. MINERAL LEASE NUMBER (FEDERAL, INDIAN, OR STATE) Patented			11. MINERAL OWNERSHIP FEDERAL <input type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input type="checkbox"/> FEE <input checked="" type="checkbox"/>			12. SURFACE OWNERSHIP FEDERAL <input type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input type="checkbox"/> FEE <input checked="" type="checkbox"/>					
13. NAME OF SURFACE OWNER (if box 12 = 'fee') Dart Homestead Ranch, Inc.						14. SURFACE OWNER PHONE (if box 12 = 'fee') 435-722-7087					
15. ADDRESS OF SURFACE OWNER (if box 12 = 'fee') Route 2, Box 2044, Roosevelt, UT 84066						16. SURFACE OWNER E-MAIL (if box 12 = 'fee')					
17. INDIAN ALLOTTEE OR TRIBE NAME (if box 12 = 'INDIAN')			18. INTEND TO COMMINGLE PRODUCTION FROM MULTIPLE FORMATIONS YES <input type="checkbox"/> (Submit Commingling Application) NO <input checked="" type="checkbox"/>			19. SLANT VERTICAL <input type="checkbox"/> DIRECTIONAL <input type="checkbox"/> HORIZONTAL <input checked="" type="checkbox"/>					
20. LOCATION OF WELL		FOOTAGES		QTR-QTR	SECTION	TOWNSHIP		RANGE		MERIDIAN	
LOCATION AT SURFACE		250 FNL 201 FWL		NWNW	14	3.0 S		2.0 W		U	
Top of Uppermost Producing Zone		660 FNL 660 FWL		NWNW	14	3.0 S		2.0 W		U	
At Total Depth		660 FSL 660 FWL		SWSW	14	3.0 S		2.0 W		U	
21. COUNTY UINTAH			22. DISTANCE TO NEAREST LEASE LINE (Feet) 201			23. NUMBER OF ACRES IN DRILLING UNIT 40					
			25. DISTANCE TO NEAREST WELL IN SAME POOL (Applied For Drilling or Completion) 3000			26. PROPOSED DEPTH MD: 13332 TVD: 8765					
27. ELEVATION - GROUND LEVEL 5418			28. BOND NUMBER B001834			29. SOURCE OF DRILLING WATER / WATER RIGHTS APPROVAL NUMBER IF APPLICABLE 437478					
Hole, Casing, and Cement Information											
String	Hole Size	Casing Size	Length	Weight	Grade & Thread	Max Mud Wt.	Cement	Sacks	Yield	Weight	
Cond	17.5	14	0 - 100	37.0	H-40 ST&C	0.0	Hi Lift "G"	35	1.17	15.8	
Surf	12.25	9.625	0 - 2500	36.0	J-55 LT&C	8.3	Type III	216	3.33	11.0	
							Type III	95	1.9	13.0	
I1	8.75	7	0 - 9348	29.0	P-110 Other	11.5	35/65 Poz	277	2.59	11.5	
							50/50 Poz	287	1.62	13.0	
Prod	6.125	4.5	8416 - 13332	13.5	P-110 Other	11.5	No Used	0	0.0	0.0	
ATTACHMENTS											
VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES											
<input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER						<input checked="" type="checkbox"/> COMPLETE DRILLING PLAN					
<input checked="" type="checkbox"/> AFFIDAVIT OF STATUS OF SURFACE OWNER AGREEMENT (IF FEE SURFACE)						<input type="checkbox"/> FORM 5. IF OPERATOR IS OTHER THAN THE LEASE OWNER					
<input checked="" type="checkbox"/> DIRECTIONAL SURVEY PLAN (IF DIRECTIONALLY OR HORIZONTALLY DRILLED)						<input checked="" type="checkbox"/> TOPOGRAPHICAL MAP					
NAME Don Hamilton				TITLE Permitting Agent				PHONE 435 719-2018			
SIGNATURE				DATE 02/28/2013				EMAIL starpoint@etv.net			
API NUMBER ASSIGNED 43047536560000						APPROVAL					

Received: May 02, 2013

Newfield Production Company

4-14-3-2

Surface Hole Location: 250' FNL, 201' FWL, Section 14, T3S, R2W

Bottom Hole Location: 660' FSL, 660' FWL, Section 14, T3S, R2W

Duchesne County, UT

Drilling Program

1. Formation Tops

Uinta	surface
Green River	3,827'
Garden Gulch member	6,657'
Uteland Butte	8,905'
Lateral TD	8,765' TVD / 13,332' MD

2. Depth to Oil, Gas, Water, or Minerals

Base of moderately saline	1,530'	(water)
Green River	6,657' - 8,765'	(oil)

3. Pressure Control

<u>Section</u>	<u>BOP Description</u>
----------------	------------------------

Surface	12-1/4" diverter
---------	------------------

Interm/Prod	The BOP and related equipment shall meet the minimum requirements of Onshore Oil and Gas Order No. 2 for equipment and testing requirements, procedures, etc for a 5M system.
-------------	---

A 5M BOP system will consist of 2 ram preventers (double or two singles) and an annular preventer (see attached diagram). A choke manifold rated to at least 5,000 psi will be used.

4. Casing

Description	Interval		Weight (ppf)	Grade	Coupl	Pore Press @ Shoe	MW @ Shoe	Frac Grad @ Shoe	Safety Factors		
	Top	Bottom (TVD/MD)							Burst	Collapse	Tension
Conductor 14	0'	60'	37	H-40	Weld	--	--	--	--	--	--
Surface 9 5/8	0'	2,500'	36	J-55	LTC	8.33	8.33	12	3,520	2,020	453,000
Intermediate 7	0'	8,958' 9,348'	29	P-110	BTC	11	11.5	15	11,220	8,510	929,000
Production 4 1/2	8,416'	8,765' 13,332'	13.5	P-110	BTC	11	11.5	--	12,410	10,670	422,000
									3.00	2.44	6.36

Assumptions:

Surface casing MASP = (frac gradient + 1.0 ppg) - (gas gradient)

Intermediate casing MASP = (reservoir pressure) - (gas gradient)

Received: February 28, 2013

Production casing MASP = (reservoir pressure) - (gas gradient)
 All collapse calculations assume fully evacuated casing with a gas gradient
 All tension calculations assume air weight of casing
 Gas gradient = 0.1 psi/ft

All casing shall be new.

All casing strings shall have a minimum of 1 centralizer on each of the bottom 3 joints.

5. Cement

Job	Hole Size	Fill	Slurry Description	ft ³	OH excess	Weight (ppg)	Yield (ft ³ /sk)
				sacks			
Conductor	17 1/2	60'	Class G w/ 2% KCl + 0.25 lbs/sk Cello Flake	41	15%	15.8	1.17
				35			
Surface Lead	12 1/4	2,000'	Type III + .125 lbs/sk Cello Flakes	720	15%	11.0	3.33
				216			
Surface Tail	12 1/4	500'	Type III + .125 lbs/sk Cello Flakes	180	15%	13.0	1.9
				95			
Intermediate Lead	8 3/4	4,157'	Premium - 65% Class G / 35% Poz + 10% Bentonite	719	15%	11.5	2.59
				277			
Intermediate Tail	8 3/4	2,691'	50/50 Poz/Class G + 1% bentonite	465	15%	13.0	1.62
				287			
Production	6 1/8	--	Liner will not be cemented. It will be isolated with a liner top packer.	--	--	--	--
				--			

The surface casing will be cemented to surface. In the event that cement does not reach surface during the primary cement job, a remedial job will be performed.

Actual cement volumes for the intermediate casing string will be calculated from an open hole caliper log, plus 15% excess.

The cement slurries will be adjusted for hole conditions and blend test results.

The production liner will be left uncemented. Individual frac stages will be isolated with open hole packers. A liner top hanger and packer will be installed 50' above KOP.

6. Type and Characteristics of Proposed Circulating Medium

<u>Interval</u>	<u>Description</u>
Surface - 2,500'	An air and/or fresh water system will be utilized. If an air rig is used, the blooie line discharge may be less than 100' from the wellbore in order to minimize location size. The blooie line is not equipped with an automatic igniter. The air compressor may be located less than 100' from the well bore due to the low possibility of combustion with the air/dust mixture. Water will be on location to be used as kill fluid, if necessary.
2,500' - TD	A water based mud system will be utilized. Hole stability may be improved with additions of KCl or a similar inhibitive substance. In order to control formation pressure the system will be weighted with additions of bentonite, and

if conditions warrant, with barite.

-or-

A diesel based OBM system: with an oil to water ratio between 70/30 and 80/20. Emulsifiers and wetting agents will be used to maintain adequate mud properties. A water phase salinity will be maintained in the range of 25% using CaCl (Calcium Chloride).

Anticipated maximum mud weight is 11.5 ppg.

7. Logging, Coring, and Testing

Logging: A dual induction, gamma ray, and caliper log will be run in the intermediate section from the top of the curve to the base of the surface casing. A compensated neutron/formation density log will be run in the intermediate section from the top of the curve to the top of the Garden Gulch formation. A cement bond log will be run from the top of the curve to the cement top behind the intermediate casing.

Cores: As deemed necessary.

DST: There are no DST's planned for this well.

8. Anticipated Abnormal Pressure or Temperature

Maximum anticipated bottomhole pressure will be approximately equal to total depth (feet) multiplied by a 0.57 psi/ft gradient.

$$8,765' \times 0.57 \text{ psi/ft} = 5014 \text{ psi}$$

No abnormal temperature is expected. No H₂S is expected.

9. Other Aspects

An 8-3/4" vertical hole will be drilled to a kick off point of 8,466'.

Directional tools will then be used to build to 92.90 degrees inclination.

The 7" intermediate casing string will be set once the well is landed horizontally in the target zone.

The lateral will be drilled to the bottomhole location shown on the plat.

A liner with a system of open hole packers will be used to provide multi-stage frac isolation in the lateral. The top of the liner will be placed 50' above KOP and will be isolated with a liner top packer.

Newfield requests the following variances from Onshore Order #2:

- Variance from Onshore Order #2, III.E.1

Refer to Newfield Production Company Standard Operating Practices "Ute Tribal Green River Development Program" paragraph 9.0

If oil based mud (OBM) is used, all processed OBM drill cuttings would be removed from the well bore using a closed loop system. OBM cuttings would be dried and centrifuged and then temporarily stored within a lined pit that would be constructed inboard of the pad area. The pit would be lined with 16 mil (minimum) thickness polyethylene nylon reinforced liner material. The liner(s) would overlay straw, dirt and/or bentonite if rock is encountered during excavation. The liner would overlap the pit walls and be covered with dirt and/or rocks to hold them in place. No trash, scrap pipe, or other materials that could puncture the liner would be discarded in the pit, and a minimum of two feet of free board would be maintained between the maximum fluid level and the top of the pit at all times. All OBM cuttings will be mechanically dried and centrifuged so that they can be easily transferred to a lined cuttings pit with little to no free fluid on them. Samples of the mechanically dried OBM cuttings will be taken for chemical analysis. The OBM cuttings will then be mixed with a chemical drying agent and the chemically dried OBM cuttings will be placed in a lined cuttings pit on the generating location that is separated from the water based cuttings. The pit will be of sufficient size to contain all cuttings generated in the drilling process. At this point, the chemically dried OBM cuttings are ready for the Firmus® construction process or the OBM cuttings may also be transported to a state approved disposal facility. If an oil based mud is not used, a conventional reserve pit will be utilized. The pit will be reclaimed using UDOGM and BLM approved procedures.

CONFIDENTIAL
Returned Unapproved

T3S, R2W, U.S.B.&M.

NEWFIELD EXPLORATION COMPANY


Well location, #4-14-3-2WH, located as shown in the NW 1/4 NW 1/4 of Section 14, T3S, R2W, U.S.B.&M., Duchesne County, Utah.

BASIS OF ELEVATION

SPOT ELEVATION LOCATED AT THE NORTHEAST CORNER OF SECTION 20, T3S, R2W, U.S.B.&M. TAKEN FROM THE MYTON, QUADRANGLE, UTAH, DUCHESNE COUNTY, 7.5 MINUTE QUAD (TOPOGRAPHIC MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 5148 FEET.

BASIS OF BEARINGS

BASIS OF BEARINGS IS A G.P.S. OBSERVATION.



CERTIFICATE


THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

REGISTERED LAND SURVEYOR
REGISTRATION NO. 161319
STATE OF UTAH

UINTAH ENGINEERING & LAND SURVEYING
85 SOUTH 200 EAST - VERNAL, UTAH 84078
(435) 789-1017

SCALE 1" = 1000'	DATE SURVEYED: 11-12-12	DATE DRAWN: 11-15-12
PARTY M.A. A.H. S.F.	REFERENCES G.L.O. PLAT	
WEATHER COLD	FILE NEWFIELD EXPLORATION COMPANY	

Received: February 28, 2013



LEGEND:

└─┐ = 90° SYMBOL

● = PROPOSED WELL HEAD.

▲ = SECTION CORNERS LOCATED.

△ = SECTION CORNERS
RE-ESTABLISHED. (Not Set
on Ground.)

LINE TABLE

LINE	DIRECTION	LENGTH
L1	S48°12'59"E	616.52'

NAD 83 (TOP OF PRODUCING FORMATION)	NAD 83 (TARGET BOTTOM HOLE)	NAD 83 (SURFACE LOCATION)
LATITUDE = 40°13'39.87" (40.227742)	LATITUDE = 40°13'00.54" (40.216817)	LATITUDE = 40°13'43.93" (40.228869)
LONGITUDE = 110°05'02.01" (110.083892)	LONGITUDE = 110°05'01.31" (110.083697)	LONGITUDE = 110°05'07.93" (110.085536)
NAD 27 (TOP OF PRODUCING FORMATION)	NAD 27 (TARGET BOTTOM HOLE)	NAD 27 (SURFACE LOCATION)
LATITUDE = 40°13'40.02" (40.227783)	LATITUDE = 40°13'00.69" (40.216858)	LATITUDE = 40°13'44.08" (40.228911)
LONGITUDE = 110°04'59.47" (110.083186)	LONGITUDE = 110°04'58.77" (110.082992)	LONGITUDE = 110°05'05.39" (110.084831)

NEWFIELD EXPLORATION COMPANY


#4-14-3-2WH

SECTION 14, T3S, R2W, U.S.B.&M.

PROCEED IN A SOUTHERLY, THEN SOUTHWESTERLY, THEN SOUTHERLY DIRECTION FROM ROOSEVELT, UTAH ALONG U.S. HIGHWAY 40 APPROXIMATELY 7.2 MILES TO THE BEGINNING OF THE PROPOSED ACCESS FOR THE #4-15-3-2WH TO THE WEST; FOLLOW ROAD FLAGS IN A WESTERLY, THEN SOUTHWESTERLY, THEN NORTHWESTERLY, THEN NORTHEASTERLY DIRECTION APPROXIMATELY 10,732' TO THE BEGINNING OF THE PROPOSED ACCESS TO THE SOUTHEAST; FOLLOW ROAD FLAGS IN A SOUTHEASTERLY, THEN EASTERLY DIRECTION APPROXIMATELY 2,668' TO THE PROPOSED LOCATION.

TOTAL DISTANCE FROM ROOSEVELT, UTAH TO THE PROPOSED LOCATION IS APPROXIMATELY 9.7 MILES.

CONFIDENTIAL
Returned Unapproved



LEGEND:

PROPOSED LOCATION



Uintah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813

NEWFIELD EXPLORATION COMPANY


#4-14-3-2WH
 SECTION 14, T3S, R2W, U.S.B.&M.
 250' FNL 201' FWL

ACCESS ROAD
 MAP

11 20 12
 MONTH DAY YEAR

SCALE: 1:100,000 DRAWN BY: C.L. REVISED: 00-00-00





LEGEND:

- EXISTING ROAD
- PROPOSED ACCESS ROAD
- 1 18" CMP REQUIRED 2 24" CMP REQUIRED




Uintah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813



NEWFIELD EXPLORATION COMPANY

#4-14-3-2WH
 SECTION 14, T3S, R2W, U.S.B.&M.
 250' FNL 201' FWL

ACCESS ROAD MAP	11	20	12	B TOPO
	MONTH	DAY	YEAR	
SCALE: 1" = 2000'	DRAWN BY: C.L.			REVISED: 00-00-00



LEGEND:

- ⊗ DISPOSAL WELLS
- PRODUCING WELLS
- ⬮ SHUT IN WELLS
- ⬮ ABANDONED WELLS
- ⬮ TEMPORARILY ABANDONED

Uintah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
(435) 789-1017 * FAX (435) 789-1813


NEWFIELD EXPLORATION COMPANY

#4-14-3-2WH
SECTION 14, T3S, R2W, U.S.B.&M.
250' FNL 201' FWL

TOPOGRAPHIC
MAP

SCALE: 1" = 2000' DRAWN BY: C.L. REVISED: 00-00-00

11 MONTH
20 DAY
12 YEAR



APPROXIMATE TOTAL PIPELINE DISTANCE = 25' +/-

LEGEND:

- PROPOSED ACCESS ROAD
- EXISTING PIPELINE
- - - - PROPOSED PIPELINE
- - - - PROPOSED PIPELINE (SERVICING OTHER WELLS)

NEWFIELD EXPLORATION COMPANY

#4-14-3-2WH
SECTION 14, T3S, R2W, U.S.B.&M.
250' FNL 201' FWL



Uintah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
(435) 789-1017 * FAX (435) 789-1813



**TOPOGRAPHIC
MAP**

SCALE: 1" = 2000'

DRAWN BY: C.L.

11 20 12
MONTH DAY YEAR

REVISED: 00-00-00



Newfield Exploration Company

Duchesne County, UT

Sec. 14-T3S-R2W

4-14-3-2WH

Plan A Rev 0 Permit

Plan: Plan A Rev 0 Proposed Permit Only

Sperry Drilling Services

Proposal Report

23 January, 2013

Well Coordinates: 2,211,393.80 N, 620,367.94 E (40° 13' 43.93" N, 110° 05' 07.93" W)

Ground Level: 5,418.00 ft

Local Coordinate Origin:

Centered on Site Sec. 14-T3S-R2W

Viewing Datum:

WELL @ 5436.0ft (Original Well Elev)

TVDs to System:

N

North Reference:

True

Unit System:

API

Geodetic Scale Factor Applied

Version: 5000.1 Build: 61

HALLIBURTON

Received: February 28, 2013

Project: Duchesne County, UT
Site: Sec. 14-T3S-R2W
Well: 4-14-3-2WH
Wellbore: Plan A Rev 0 Permit
Design: Plan A Rev 0 Proposed Permit Only

Newfield Exploration Company




HALLIBURTON
Sperry Drilling

SECTION DETAILS

Sec	MD	Inc	Azi	TVD	+N/-S	+E/-W	Dleg	TFace	VSec	Target
1	0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.0	
2	3000.0	0.00	0.00	3000.0	0.0	0.0	0.00	0.00	0.0	
3	3466.7	7.00	68.95	3465.5	10.2	26.6	1.50	68.95	-7.1	
4	6966.7	7.00	68.95	6939.4	163.4	424.6	0.00	0.00	-113.0	
5	7433.3	0.00	0.00	7404.9	173.7	451.2	1.50	180.00	-120.1	
6	8465.7	0.00	0.00	8437.3	173.7	451.2	0.00	0.00	-120.1	
7	9283.3	89.93	179.22	8958.2	-346.5	458.3	11.00	179.22	397.4	4-14-3-2 CP_Tgt
8	9347.6	89.93	179.22	8958.2	-410.8	459.2	0.00	0.00	461.4	
9	9497.6	89.93	179.22	8958.4	-560.8	461.2	0.00	0.00	610.6	
10	9597.6	92.93	179.22	8955.9	-660.8	462.6	3.00	-0.06	710.0	
11	13332.9	92.93	179.22	8765.0	-4390.8	513.6	0.00	0.00	4420.8	4-14-3-2 BHL_Tgt

WELLBORE TARGET DETAILS (MAP CO-ORDINATES AND LAT/LONG)

Name	TVD	+N/-S	+E/-W	Northing	Easting	Latitude	Longitude	Shape
4-14-3-2 SL_Tgt	0.0	0.0	0.0	2211393.80	620367.94	40° 13' 43.930 N	110° 5' 7.930 W	Point
Sec 14 Lines	0.0	0.0	0.0	2211393.80	620367.94	40° 13' 43.930 N	110° 5' 7.930 W	Polygon
Sec 14 Setbacks	0.0	0.0	0.0	2211393.80	620367.94	40° 13' 43.930 N	110° 5' 7.930 W	Polygon
4-14-3-2 BHL_Tgt	8765.0	-4390.8	513.6	2210058.22	620545.61	40° 13' 0.540 N	110° 5' 1.310 W	Point
4-14-3-2 CP_Tgt	8958.0	-410.8	459.2	2211270.31	620509.85	40° 13' 39.870 N	110° 5' 2.010 W	Point



WELL DETAILS: 4-14-3-2WH

Ground Level: 5418.0			
Northing	Easting	Latitude	Longitude
2211393.80	620367.94	40° 13' 43.930 N	110° 5' 7.930 W

Plan A Rev 0 Proposed Permit Only (4-14-3-2WH)

Created By: Lacy Boughdadly Date: 1/23/2013

Checked: _____ Date: _____

Received: February 28, 2013

HALLIBURTON**Plan Report for 4-14-3-2WH - Plan A Rev 0 Proposed Permit Only**

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	Toolface Azimuth (°)
0.0	0.00	0.00	0.0	0.0	0.0	0.0	0.00	0.00	0.00	0.00
100.0	0.00	0.00	100.0	0.0	0.0	0.0	0.00	0.00	0.00	0.00
200.0	0.00	0.00	200.0	0.0	0.0	0.0	0.00	0.00	0.00	0.00
300.0	0.00	0.00	300.0	0.0	0.0	0.0	0.00	0.00	0.00	0.00
400.0	0.00	0.00	400.0	0.0	0.0	0.0	0.00	0.00	0.00	0.00
500.0	0.00	0.00	500.0	0.0	0.0	0.0	0.00	0.00	0.00	0.00
600.0	0.00	0.00	600.0	0.0	0.0	0.0	0.00	0.00	0.00	0.00
700.0	0.00	0.00	700.0	0.0	0.0	0.0	0.00	0.00	0.00	0.00
800.0	0.00	0.00	800.0	0.0	0.0	0.0	0.00	0.00	0.00	0.00
900.0	0.00	0.00	900.0	0.0	0.0	0.0	0.00	0.00	0.00	0.00
1,000.0	0.00	0.00	1,000.0	0.0	0.0	0.0	0.00	0.00	0.00	0.00
1,100.0	0.00	0.00	1,100.0	0.0	0.0	0.0	0.00	0.00	0.00	0.00
1,200.0	0.00	0.00	1,200.0	0.0	0.0	0.0	0.00	0.00	0.00	0.00
1,300.0	0.00	0.00	1,300.0	0.0	0.0	0.0	0.00	0.00	0.00	0.00
1,400.0	0.00	0.00	1,400.0	0.0	0.0	0.0	0.00	0.00	0.00	0.00
1,500.0	0.00	0.00	1,500.0	0.0	0.0	0.0	0.00	0.00	0.00	0.00
1,600.0	0.00	0.00	1,600.0	0.0	0.0	0.0	0.00	0.00	0.00	0.00
1,700.0	0.00	0.00	1,700.0	0.0	0.0	0.0	0.00	0.00	0.00	0.00
1,800.0	0.00	0.00	1,800.0	0.0	0.0	0.0	0.00	0.00	0.00	0.00
1,900.0	0.00	0.00	1,900.0	0.0	0.0	0.0	0.00	0.00	0.00	0.00
2,000.0	0.00	0.00	2,000.0	0.0	0.0	0.0	0.00	0.00	0.00	0.00
2,100.0	0.00	0.00	2,100.0	0.0	0.0	0.0	0.00	0.00	0.00	0.00
2,200.0	0.00	0.00	2,200.0	0.0	0.0	0.0	0.00	0.00	0.00	0.00
2,300.0	0.00	0.00	2,300.0	0.0	0.0	0.0	0.00	0.00	0.00	0.00
2,400.0	0.00	0.00	2,400.0	0.0	0.0	0.0	0.00	0.00	0.00	0.00
2,500.0	0.00	0.00	2,500.0	0.0	0.0	0.0	0.00	0.00	0.00	0.00
2,600.0	0.00	0.00	2,600.0	0.0	0.0	0.0	0.00	0.00	0.00	0.00
2,700.0	0.00	0.00	2,700.0	0.0	0.0	0.0	0.00	0.00	0.00	0.00
2,800.0	0.00	0.00	2,800.0	0.0	0.0	0.0	0.00	0.00	0.00	0.00
2,900.0	0.00	0.00	2,900.0	0.0	0.0	0.0	0.00	0.00	0.00	0.00
3,000.0	0.00	0.00	3,000.0	0.0	0.0	0.0	0.00	0.00	0.00	0.00
3,100.0	1.50	68.95	3,100.0	0.5	1.2	-0.3	1.50	1.50	0.00	68.95
3,200.0	3.00	68.95	3,199.9	1.9	4.9	-1.3	1.50	1.50	0.00	0.00
3,300.0	4.50	68.95	3,299.7	4.2	11.0	-2.9	1.50	1.50	0.00	0.00
3,400.0	6.00	68.95	3,399.3	7.5	19.5	-5.2	1.50	1.50	0.00	0.00
3,466.7	7.00	68.95	3,465.5	10.2	26.6	-7.1	1.50	1.50	0.00	0.00
3,500.0	7.00	68.95	3,498.6	11.7	30.4	-8.1	0.00	0.00	0.00	0.00
3,600.0	7.00	68.95	3,597.8	16.1	41.7	-11.1	0.00	0.00	0.00	0.00
3,700.0	7.00	68.95	3,697.1	20.4	53.1	-14.1	0.00	0.00	0.00	0.00
3,800.0	7.00	68.95	3,796.4	24.8	64.5	-17.2	0.00	0.00	0.00	0.00
3,900.0	7.00	68.95	3,895.6	29.2	75.9	-20.2	0.00	0.00	0.00	0.00
4,000.0	7.00	68.95	3,994.9	33.6	87.2	-23.2	0.00	0.00	0.00	0.00
4,100.0	7.00	68.95	4,094.1	37.9	98.6	-26.2	0.00	0.00	0.00	0.00
4,200.0	7.00	68.95	4,193.4	42.3	110.0	-29.3	0.00	0.00	0.00	0.00
4,300.0	7.00	68.95	4,292.6	46.7	121.4	-32.3	0.00	0.00	0.00	0.00
4,400.0	7.00	68.95	4,391.9	51.1	132.7	-35.3	0.00	0.00	0.00	0.00
4,500.0	7.00	68.95	4,491.1	55.5	144.1	-38.3	0.00	0.00	0.00	0.00
4,600.0	7.00	68.95	4,590.4	59.8	155.5	-41.4	0.00	0.00	0.00	0.00
4,700.0	7.00	68.95	4,689.6	64.2	166.8	-44.4	0.00	0.00	0.00	0.00
4,800.0	7.00	68.95	4,788.9	68.6	178.2	-47.4	0.00	0.00	0.00	0.00
4,900.0	7.00	68.95	4,888.2	73.0	189.6	-50.4	0.00	0.00	0.00	0.00
5,000.0	7.00	68.95	4,987.4	77.3	201.0	-53.5	0.00	0.00	0.00	0.00
5,100.0	7.00	68.95	5,086.7	81.7	212.3	-56.5	0.00	0.00	0.00	0.00
5,200.0	7.00	68.95	5,185.9	86.1	223.7	-59.5	0.00	0.00	0.00	0.00
5,300.0	7.00	68.95	5,285.2	90.5	235.1	-62.6	0.00	0.00	0.00	0.00
5,400.0	7.00	68.95	5,384.4	94.9	246.5	-65.6	0.00	0.00	0.00	0.00
5,500.0	7.00	68.95	5,483.7	99.2	257.8	-68.6	0.00	0.00	0.00	0.00
5,600.0	7.00	68.95	5,582.9	103.6	269.2	-71.6	0.00	0.00	0.00	0.00
5,700.0	7.00	68.95	5,682.2	108.0	280.6	-74.7	0.00	0.00	0.00	0.00

Received: February 28, 2013

HALLIBURTON**Plan Report for 4-14-3-2WH - Plan A Rev 0 Proposed Permit Only**

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	Toolface Azimuth (°)
5,800.0	7.00	68.95	5,781.4	112.4	292.0	-77.7	0.00	0.00	0.00	0.00
5,900.0	7.00	68.95	5,880.7	116.7	303.3	-80.7	0.00	0.00	0.00	0.00
6,000.0	7.00	68.95	5,980.0	121.1	314.7	-83.7	0.00	0.00	0.00	0.00
6,100.0	7.00	68.95	6,079.2	125.5	326.1	-86.8	0.00	0.00	0.00	0.00
6,200.0	7.00	68.95	6,178.5	129.9	337.5	-89.8	0.00	0.00	0.00	0.00
6,300.0	7.00	68.95	6,277.7	134.2	348.8	-92.8	0.00	0.00	0.00	0.00
6,400.0	7.00	68.95	6,377.0	138.6	360.2	-95.8	0.00	0.00	0.00	0.00
6,500.0	7.00	68.95	6,476.2	143.0	371.6	-98.9	0.00	0.00	0.00	0.00
6,600.0	7.00	68.95	6,575.5	147.4	382.9	-101.9	0.00	0.00	0.00	0.00
6,700.0	7.00	68.95	6,674.7	151.8	394.3	-104.9	0.00	0.00	0.00	0.00
6,800.0	7.00	68.95	6,774.0	156.1	405.7	-108.0	0.00	0.00	0.00	0.00
6,900.0	7.00	68.95	6,873.2	160.5	417.1	-111.0	0.00	0.00	0.00	0.00
6,966.7	7.00	68.95	6,939.4	163.4	424.6	-113.0	0.00	0.00	0.00	0.00
7,000.0	6.50	68.95	6,972.5	164.8	428.3	-114.0	1.50	-1.50	0.00	180.00
7,100.0	5.00	68.95	7,072.0	168.4	437.7	-116.5	1.50	-1.50	0.00	180.00
7,200.0	3.50	68.95	7,171.7	171.1	444.6	-118.3	1.50	-1.50	0.00	180.00
7,300.0	2.00	68.95	7,271.6	172.8	449.1	-119.5	1.50	-1.50	0.00	180.00
7,400.0	0.50	68.95	7,371.6	173.6	451.1	-120.0	1.50	-1.50	0.00	180.00
7,433.3	0.00	0.00	7,404.9	173.7	451.2	-120.1	1.50	-1.50	0.00	-180.00
7,500.0	0.00	0.00	7,471.6	173.7	451.2	-120.1	0.00	0.00	0.00	0.00
7,600.0	0.00	0.00	7,571.6	173.7	451.2	-120.1	0.00	0.00	0.00	0.00
7,700.0	0.00	0.00	7,671.6	173.7	451.2	-120.1	0.00	0.00	0.00	0.00
7,800.0	0.00	0.00	7,771.6	173.7	451.2	-120.1	0.00	0.00	0.00	0.00
7,900.0	0.00	0.00	7,871.6	173.7	451.2	-120.1	0.00	0.00	0.00	0.00
8,000.0	0.00	0.00	7,971.6	173.7	451.2	-120.1	0.00	0.00	0.00	0.00
8,100.0	0.00	0.00	8,071.6	173.7	451.2	-120.1	0.00	0.00	0.00	0.00
8,200.0	0.00	0.00	8,171.6	173.7	451.2	-120.1	0.00	0.00	0.00	0.00
8,300.0	0.00	0.00	8,271.6	173.7	451.2	-120.1	0.00	0.00	0.00	0.00
8,400.0	0.00	0.00	8,371.6	173.7	451.2	-120.1	0.00	0.00	0.00	0.00
8,465.7	0.00	0.00	8,437.1	173.7	451.2	-120.1	0.00	0.00	0.00	0.00
KOP at 8465.7 ft										
8,500.0	3.77	179.22	8,471.6	172.5	451.2	-118.9	11.00	11.00	0.00	179.22
8,550.0	9.27	179.22	8,521.2	166.9	451.3	-113.3	11.00	11.00	0.00	0.00
8,600.0	14.77	179.22	8,570.1	156.4	451.5	-102.9	11.00	11.00	0.00	0.00
8,650.0	20.27	179.22	8,617.8	141.4	451.7	-88.0	11.00	11.00	0.00	0.00
8,700.0	25.77	179.22	8,663.8	121.8	451.9	-68.5	11.00	11.00	0.00	0.00
8,750.0	31.27	179.22	8,707.7	98.0	452.3	-44.8	11.00	11.00	0.00	0.00
8,800.0	36.77	179.22	8,749.1	70.0	452.6	-17.0	11.00	11.00	0.00	0.00
8,850.0	42.27	179.22	8,787.7	38.2	453.1	14.7	11.00	11.00	0.00	0.00
8,900.0	47.77	179.22	8,823.0	2.9	453.5	49.8	11.00	11.00	0.00	0.00
8,950.0	53.27	179.22	8,854.8	-35.7	454.1	88.2	11.00	11.00	0.00	0.00
9,000.0	58.77	179.22	8,882.7	-77.1	454.6	129.4	11.00	11.00	0.00	0.00
9,050.0	64.27	179.22	8,906.5	-121.1	455.2	173.1	11.00	11.00	0.00	0.00
9,100.0	69.77	179.22	8,926.0	-167.1	455.9	218.9	11.00	11.00	0.00	0.00
9,150.0	75.27	179.22	8,941.1	-214.8	456.5	266.3	11.00	11.00	0.00	0.00
9,200.0	80.77	179.22	8,951.4	-263.6	457.2	315.0	11.00	11.00	0.00	0.00
9,250.0	86.27	179.22	8,957.1	-313.3	457.9	364.4	11.00	11.00	0.00	0.00
9,283.3	89.93	179.22	8,958.2	-346.6	458.3	397.5	10.98	10.98	0.00	0.00
End Build at 9283.3 ft										
9,300.0	89.93	179.22	8,958.2	-363.3	458.5	414.1	0.00	0.00	0.00	0.00
9,347.6	89.93	179.22	8,958.2	-410.9	459.2	461.4	0.00	0.00	0.00	0.00
Casing Point at 9347.6 MD & 8958.2 TVD - 7"										
9,400.0	89.93	179.22	8,958.3	-463.3	459.9	513.6	0.00	0.00	0.00	0.00
9,497.6	89.93	179.22	8,958.4	-560.8	461.2	610.6	0.00	0.00	0.00	0.00
9,500.0	90.00	179.22	8,958.4	-563.3	461.3	613.0	3.00	3.00	0.00	-0.06
9,597.6	92.93	179.22	8,955.9	-660.8	462.6	710.0	3.00	3.00	0.00	-0.06
9,600.0	92.93	179.22	8,955.8	-663.2	462.6	712.4	0.00	0.00	0.00	0.00
9,700.0	92.93	179.22	8,950.7	-763.1	464.0	811.8	0.00	0.00	0.00	0.00
9,800.0	92.93	179.22	8,945.6	-862.9	465.3	911.1	0.00	0.00	0.00	0.00

Plan Report for 4-14-3-2WH - Plan A Rev 0 Proposed Permit Only

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	Toolface Azimuth (°)
9,900.0	92.93	179.22	8,940.5	-962.8	466.7	1,010.5	0.00	0.00	0.00	0.00
10,000.0	92.93	179.22	8,935.4	-1,062.6	468.1	1,109.8	0.00	0.00	0.00	0.00
10,100.0	92.93	179.22	8,930.3	-1,162.5	469.4	1,209.2	0.00	0.00	0.00	0.00
10,200.0	92.93	179.22	8,925.1	-1,262.4	470.8	1,308.5	0.00	0.00	0.00	0.00
10,300.0	92.93	179.22	8,920.0	-1,362.2	472.2	1,407.8	0.00	0.00	0.00	0.00
10,400.0	92.93	179.22	8,914.9	-1,462.1	473.5	1,507.2	0.00	0.00	0.00	0.00
10,500.0	92.93	179.22	8,909.8	-1,561.9	474.9	1,606.5	0.00	0.00	0.00	0.00
10,600.0	92.93	179.22	8,904.7	-1,661.8	476.3	1,705.9	0.00	0.00	0.00	0.00
10,700.0	92.93	179.22	8,899.6	-1,761.7	477.6	1,805.2	0.00	0.00	0.00	0.00
10,800.0	92.93	179.22	8,894.5	-1,861.5	479.0	1,904.6	0.00	0.00	0.00	0.00
10,900.0	92.93	179.22	8,889.4	-1,961.4	480.4	2,003.9	0.00	0.00	0.00	0.00
11,000.0	92.93	179.22	8,884.3	-2,061.2	481.7	2,103.2	0.00	0.00	0.00	0.00
11,100.0	92.93	179.22	8,879.1	-2,161.1	483.1	2,202.6	0.00	0.00	0.00	0.00
11,200.0	92.93	179.22	8,874.0	-2,261.0	484.5	2,301.9	0.00	0.00	0.00	0.00
11,300.0	92.93	179.22	8,868.9	-2,360.8	485.8	2,401.3	0.00	0.00	0.00	0.00
11,400.0	92.93	179.22	8,863.8	-2,460.7	487.2	2,500.6	0.00	0.00	0.00	0.00
11,500.0	92.93	179.22	8,858.7	-2,560.5	488.5	2,600.0	0.00	0.00	0.00	0.00
11,600.0	92.93	179.22	8,853.6	-2,660.4	489.9	2,699.3	0.00	0.00	0.00	0.00
11,700.0	92.93	179.22	8,848.5	-2,760.3	491.3	2,798.6	0.00	0.00	0.00	0.00
11,800.0	92.93	179.22	8,843.4	-2,860.1	492.6	2,898.0	0.00	0.00	0.00	0.00
11,900.0	92.93	179.22	8,838.2	-2,960.0	494.0	2,997.3	0.00	0.00	0.00	0.00
12,000.0	92.93	179.22	8,833.1	-3,059.8	495.4	3,096.7	0.00	0.00	0.00	0.00
12,100.0	92.93	179.22	8,828.0	-3,159.7	496.7	3,196.0	0.00	0.00	0.00	0.00
12,200.0	92.93	179.22	8,822.9	-3,259.6	498.1	3,295.4	0.00	0.00	0.00	0.00
12,300.0	92.93	179.22	8,817.8	-3,359.4	499.5	3,394.7	0.00	0.00	0.00	0.00
12,400.0	92.93	179.22	8,812.7	-3,459.3	500.8	3,494.0	0.00	0.00	0.00	0.00
12,500.0	92.93	179.22	8,807.6	-3,559.1	502.2	3,593.4	0.00	0.00	0.00	0.00
12,600.0	92.93	179.22	8,802.5	-3,659.0	503.6	3,692.7	0.00	0.00	0.00	0.00
12,700.0	92.93	179.22	8,797.4	-3,758.9	504.9	3,792.1	0.00	0.00	0.00	0.00
12,800.0	92.93	179.22	8,792.2	-3,858.7	506.3	3,891.4	0.00	0.00	0.00	0.00
12,900.0	92.93	179.22	8,787.1	-3,958.6	507.6	3,990.7	0.00	0.00	0.00	0.00
13,000.0	92.93	179.22	8,782.0	-4,058.4	509.0	4,090.1	0.00	0.00	0.00	0.00
13,100.0	92.93	179.22	8,776.9	-4,158.3	510.4	4,189.4	0.00	0.00	0.00	0.00
13,200.0	92.93	179.22	8,771.8	-4,258.2	511.7	4,288.8	0.00	0.00	0.00	0.00
13,300.0	92.93	179.22	8,766.7	-4,358.0	513.1	4,388.1	0.00	0.00	0.00	0.00
13,332.9	92.93	179.22	8,765.0	-4,390.8	513.6	4,420.8	0.00	0.00	0.00	0.00

TD at 13332.9 ft

Plan Annotations

Measured Depth (ft)	Vertical Depth (ft)	Local Coordinates +N/-S (ft)	+E/-W (ft)	Comment
8,465.7	8,437.3	0.0	0.0	KOP at 8465.7 ft
9,283.3	8,958.2	10.2	26.6	End Build at 9283.3 ft
9,347.6	8,958.2	163.4	424.6	Casing Point at 9347.6 MD & 8958.2 TVD
13,332.9	8,765.0	173.7	451.2	TD at 13332.9 ft

Vertical Section Information

Angle Type	Target	Azimuth (°)	Origin Type	Origin +N/_S (ft)	+E/-W (ft)	Start TVD (ft)
Target	4-14-3-2 BHL_Tgt	173.33	Slot	0.0	0.0	8,765.0

Plan Report for 4-14-3-2WH - Plan A Rev 0 Proposed Permit Only**Survey tool program**

From (ft)	To (ft)	Survey/Plan	Survey Tool
0.0	13,332.9	Plan A Rev 0 Proposed Permit Only	MWD

Casing Details

Measured Depth (ft)	Vertical Depth (ft)	Name	Casing Diameter (in)	Hole Diameter (in)
9,347.6	8,958.2	7"	7.000	7.500

Targets associated with this wellbore

Target Name	TVD (ft)	+N/-S (ft)	+E/-W (ft)	Shape
4-14-3-2 CP_Tgt	8,958.0	-410.8	459.2	Point
Sec 14 Setbacks	0.0	0.0	0.0	Polygon
4-14-3-2 SL_Tgt	0.0	0.0	0.0	Point
Sec 14 Lines	0.0	0.0	0.0	Polygon
4-14-3-2 BHL_Tgt	8,765.0	4,390.8	513.6	Point

North Reference Sheet for Sec. 14-T3S-R2W - 4-14-3-2WH - Plan A Rev 0 Permit

All data is in Feet unless otherwise stated. Directions and Coordinates are relative to True North Reference.

Vertical Depths are relative to WELL @ 5436.0ft (Original Well Elev). Northing and Easting are relative to Sec. 14-T3S-R2W

Coordinate System is US State Plane 1983, Utah Central Zone using datum North American Datum 1983, ellipsoid GRS 1980

Projection method is Lambert Conformal Conic (2 parallel)

Central Meridian is -111.50°, Longitude Origin: 0° 0' 0.000 E°, Latitude Origin: 40° 39' 0.000 N°

False Easting: 500,000.00m, False Northing: 2,000,000.00m, Scale Reduction: 0.99992240

Grid Coordinates of Well: 2,211,393.80 m N, 620,367.94 m E

Geographical Coordinates of Well: 40° 13' 43.93" N, 110° 05' 07.93" W

Grid Convergence at Surface is: 0.91°

Based upon Minimum Curvature type calculations, at a Measured Depth of 13,332.86ft the Bottom Hole Displacement is 4,420.76ft in the Direction of 173.33° (True).

Magnetic Convergence at surface is: -10.27° (23 January 2013, , BGGM2012)



**AFFIDAVIT OF EASEMENT, RIGHT-OF-WAY AND
SURFACE USE AGREEMENT**

Peter Burns personally appeared before me, being duly sworn, deposes and with respect to State of Utah R649-3-34.7 says:

1. My name is Peter Burns. I am a Landman for Newfield Production Company, whose address is 1001 17th Street, Suite 2000, Denver, CO 80202 ("Newfield").
2. Newfield is the Operator of the proposed Dart 4-14-3-2WH well with a surface location to be positioned in the NWNW of Section 14, Township 3 South, Range 2 West (the "Drillsite Location"), and a bottom hole location to be positioned in the SWSW of Section 14, Township 3 South, Range 2 West, Duchesne County, Utah. The surface owner of the Drillsite Location is Dart Homestead Ranch, Inc., whose address is Route 2, Box 2044, Roosevelt, UT 84066 ("Surface Owner").
3. Newfield and the Surface Owner have agreed upon an Easement, Right-of-Way and Surface Use Agreement dated February 16, 2013 covering the Drillsite Location and access to the Drillsite Location.

FURTHER AFFIANT SAYETH NOT.



Peter Burns

ACKNOWLEDGEMENT

STATE OF COLORADO §
 §
COUNTY OF DENVER §

Before me, a Notary Public, in and for the State, on this 19th day of February 2013, personally appeared Peter Burns, to me known to be the identical person who executed the foregoing instrument, and acknowledged to me that he executed the same as his own free and voluntary act and deed for the uses and purposes therein set forth.



NOTARY PUBLIC

My Commission Expires:



Received: February 28, 2013

AFFIDAVIT OF EASEMENT AND RIGHT-OF-WAY

Peter Burns personally appeared before me, being duly sworn, deposes and with respect to State of Utah R649-3-34.7 says:

1. My name is Peter Burns. I am a Landman for Newfield Production Company, whose address is 1001 17th Street, Suite 2000, Denver, CO 80202 ("Newfield").
2. Newfield is the Operator of the proposed Dart 4-14-3-2WH well with a surface location to be positioned in the NWNW of Section 14, Township 3 South, Range 2 West, Duchesne County, Utah (the "Drillsite Location"). The surface owner of a portion of the access road route is Mack Rideout, Personal Representative of the Estate of Sherman D. Rideout, whose address is 3634 Capstone Ave., Salt Lake City, UT 84121 ("Surface Owner").
3. Newfield and the Surface Owner have agreed upon an Easement and Right-of-Way dated December 10, 2012 covering the SWNW of Section 14, Township 3 South, Range 2 West, Duchesne County, Utah.

FURTHER AFFIANT SAYETH NOT.


Peter Burns

ACKNOWLEDGEMENT

STATE OF COLORADO

§

§

COUNTY OF DENVER

§

Before me, a Notary Public, in and for the State, on this 19th day of February, 2012, personally appeared Peter Burns, to me known to be the identical person who executed the foregoing instrument, and acknowledged to me that he executed the same as his own free and voluntary act and deed for the uses and purposes therein set forth.


NOTARY PUBLIC

My Commission Expires:



Received: February 28, 2013

AFFIDAVIT OF EASEMENT AND RIGHT-OF-WAY

Peter Burns personally appeared before me, being duly sworn, deposes and with respect to State of Utah R649-3-34.7 says:

1. My name is Peter Burns. I am a Landman for Newfield Production Company, whose address is 1001 17th Street, Suite 2000, Denver, CO 80202 ("Newfield").
2. Newfield is the Operator of the proposed Dart 4-14-3-2WH well with a surface location to be positioned in the NWNW of Section 14, Township 3 South, Range 2 West, Duchesne County, Utah (the "Drillsite Location"). The surface owner of a portion of the access road and pipeline route is William Mellema, Jr. - Trustee, whose address is P.O. Box 1198, Parker, CO 80134-1198 ("Surface Owner").
3. Newfield and the Surface Owner have agreed upon an Easement and Right-of-Way dated September 20, 2012 covering the N/2 and SE/4SW/4 of Section 15, Township 3 South, Range 2 West, Duchesne County, Utah.

FURTHER AFFIANT SAYETH NOT.



Peter Burns

ACKNOWLEDGEMENT

STATE OF COLORADO

§

§

COUNTY OF DENVER

§

Before me, a Notary Public, in and for the State, on this 19th day of February, 2012, personally appeared Peter Burns, to me known to be the identical person who executed the foregoing instrument, and acknowledged to me that he executed the same as his own free and voluntary act and deed for the uses and purposes therein set forth.




NOTARY PUBLIC

My Commission Expires:




Received: February 28, 2013

Typical 5M BOP stack configuration



Typical 5M choke manifold configuration



NEWFIELD



February 21, 2013

State of Utah
Division of Oil, Gas & Mining
ATTN: Brad Hill
P O Box 145801
Salt Lake City, UT 84114

Newfield Exploration Company

1001 17th Street | Suite 2000
Denver, Colorado 80202
PH 303-893-0102 | FAX 303-893-0103

RE: **Dart 4-14-3-2WH**
Section 14, T3S, R2W
Duchesne County, Utah

Mr. Hill,

Newfield Production Company proposes to drill the Dart 4-14-3-2WH from a surface location of 250' FNL & 201' FWL of Section 14, T3S, R2W. Newfield shall case and cement the Dart 4-14-3-2WH wellbore from the surface location to the point where the wellbore reaches the legal setback of 660' FNL and 660' FWL of Section 14, T3S, R2W. The cased and cemented portion of the wellbore shall be neither perforated nor produced. In the event a future recompletion into the cased and cemented portion of the wellbore is proposed, Newfield shall file the appropriate application with the State of Utah.

Newfield is operator of the Velma 2-11-3-2WH well, and the proposed State 4-11-3-2WH well, both located in the northern offset drilling and spacing unit (Section 11, T3S, R2W). Additionally, Newfield is the operator of the proposed Parkinson 14-15-3-2W well, located in the western offset drilling and spacing unit (Section 15, T3S, R2W). Due to the above circumstances, Newfield respectfully requests that DOGM administratively grant an exception location for the Dart 4-14-3-2WH.

If you have any questions or require further information, please do not hesitate to contact the undersigned at 303-382-4466 or by email at rnmill@newfield.com. Your consideration of this matter is greatly appreciated.

Sincerely,

Robert N. Miller II
Landman

Received: February 28, 2013

NEWFIELD EXPLORATION COMPANY

LOCATION LAYOUT FOR

#4-14-3-2WH

SECTION 14, T3S, R2W, U.S.B.&M.


250' FNL 201' FWL

FIGURE #1

SCALE: 1" = 60'

DATE: 11-15-12

DRAWN BY: S.F.



Elev. Ungraded Ground At Loc. Stake = 5418.3'

FINISHED GRADE ELEV. AT LOC. STAKE = 5416.4'

UINTAH ENGINEERING & LAND SURVEYING






85 So. 200 East * Vernal, Utah 84078 * (435) 789-1017

Received: February 28, 2013

1" = 40'
X-Section
Scale
1" = 100'
DATE: 11-15-12
DRAWN BY: S.F.

NEWFIELD EXPLORATION COMPANY
TYPICAL CROSS SECTIONS FOR
#4-14-3-2WH
SECTION 14, T3S, R2W, U.S.B.&M.
250' FNL 201' FWL

FIGURE #2



NOTE:

Topsoil should not be Stripped Below Finished Grade on Substructure Area.

APPROXIMATE ACREAGES

WELL SITE DISTURBANCE = ± 4.591 ACRES
ACCESS ROAD DISTURBANCE = ± 1.798 ACRES
TOTAL = ± 6.389 ACRES

* NOTE:
FILL QUANTITY INCLUDES 5% FOR COMPACTION

APPROXIMATE YARDAGES

(6") Topsoil Stripping = 2,430 Cu. Yds.
Remaining Location = 10,210 Cu. Yds.
TOTAL CUT = 12,640 CU. YDS.
FILL = 8,910 CU. YDS.

EXCESS MATERIAL = 3,730 Cu. Yds.
Topsoil & Pit Backfill (1/2 Pit Vol.) = 3,730 Cu. Yds.
EXCESS UNBALANCE (After Interim Rehabilitation) = 0 Cu. Yds.

UINTAH ENGINEERING & LAND SURVEYING
85 So. 200 East * Vernal, Utah 84078 * (435) 789-1017

Received: February 28, 2013

NEWFIELD EXPLORATION COMPANY

TYPICAL RIG LAYOUT FOR

#4-14-3-2WH

SECTION 14, T3S, R2W, U.S.B.&M.


250' FNL 201' FWL

FIGURE #3

SCALE: 1" = 60'

DATE: 11-15-12

DRAWN BY: S.F.



Total Pit Capacity
W/2' of Freeboard
= 8,710 Bbls.±
Total Pit Volume
= 2,590 Cu. Yds

UINTAH ENGINEERING & LAND SURVEYING


85 So. 200 East * Vernal, Utah 84078 * (435) 789-1017

Received: February 28, 2013

NEWFIELD EXPLORATION COMPANY
 PRODUCTION FACILITY LAYOUT FOR
 #4-14-3-2WH
 SECTION 14, T3S, R2W, U.S.B.&M.
 250' FNL 201' FWL

FIGURE #4

SCALE: 1" = 60'
 DATE: 11-15-12
 DRAWN BY: S.F.




RECLAIMED AREA

APPROXIMATE ACREAGES
 UN-RECLAIMED = ± 1.292 ACRES

UINTAH ENGINEERING & LAND SURVEYING
 85 So. 200 East * Vernal, Utah 84078 * (435) 789-1017


Received: February 28, 2013

CONFIDENTIAL
Returned Unapproved



API Number: 4304753656
Well Name: Dart 4-14-3-2WH
Township T03.0S Range R02.0W Section 14
Meridian: UBM
Operator: NEWFIELD PRODUCTION COMPANY
Map Prepared:
Map Produced by Diana Mason

- Units**
- | STATUS | UNIT |
|---------------|---------------|
| ACTIVE | ACTIVE |
| EXPLORATORY | EXPLORATORY |
| GAS STORAGE | GAS STORAGE |
| NF PP OIL | NF PP OIL |
| NF SECONDARY | NF SECONDARY |
| PI OIL | PI OIL |
| PP GAS | PP GAS |
| PP GEOTHERMAL | PP GEOTHERMAL |
| PP OIL | PP OIL |
| SECONDARY | SECONDARY |
| TERMINATED | TERMINATED |
- Fields**
- | STATUS | FIELD |
|------------|------------|
| Unknown | Unknown |
| ABANDONED | ABANDONED |
| ACTIVE | ACTIVE |
| COMBINED | COMBINED |
| INACTIVE | INACTIVE |
| STORAGE | STORAGE |
| TERMINATED | TERMINATED |



Well Name	NEWFIELD PRODUCTION COMPANY Dart 4-14-3-2WH 43047536560			
String	Cond	Surf	I1	Prod
Casing Size(")	14.000	9.625	7.000	4.500
Setting Depth (TVD)	60	2500	8958	8765
Previous Shoe Setting Depth (TVD)	0	60	2500	8958
Max Mud Weight (ppg)	8.3	8.3	11.5	11.5
BOPE Proposed (psi)	0	500	5000	5000
Casing Internal Yield (psi)	1000	3520	11220	12410
Operators Max Anticipated Pressure (psi)	5014			11.0

Calculations	Cond String	14.000	"
Max BHP (psi)	.052*Setting Depth*MW=	26	
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=	19	NO
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=	13	NO
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=	13	NO
Required Casing/BOPE Test Pressure=		60	psi
*Max Pressure Allowed @ Previous Casing Shoe=		0	psi *Assumes 1psi/ft frac gradient


Calculations	Surf String	9.625	"
Max BHP (psi)	.052*Setting Depth*MW=	1079	
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=	779	NO diverter, air or fresh wtr systm
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=	529	NO No expected pressure
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=	542	NO
Required Casing/BOPE Test Pressure=		2464	psi
*Max Pressure Allowed @ Previous Casing Shoe=		60	psi *Assumes 1psi/ft frac gradient

Calculations	I1 String	7.000	"
Max BHP (psi)	.052*Setting Depth*MW=	5357	
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=	4282	YES 5M BOP stack, 5M Annular, 5M kill lines,
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=	3386	YES choke manifold
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=	3936	NO OK
Required Casing/BOPE Test Pressure=		5000	psi
*Max Pressure Allowed @ Previous Casing Shoe=		2500	psi *Assumes 1psi/ft frac gradient

Calculations	Prod String	4.500	"
Max BHP (psi)	.052*Setting Depth*MW=	5241	
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=	4189	YES 5M BOPE, 5M annular, 5M kill lines,
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=	3313	YES 5M preventer
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=	5283	YES OK
Required Casing/BOPE Test Pressure=		5000	psi
*Max Pressure Allowed @ Previous Casing Shoe=		8958	psi *Assumes 1psi/ft frac gradient

43047536560000 Dart 4-14-3-2WH

Casing Schematic



Received: April 29, 2013

Well name:

43047536560000 Dart 4-14-3-2WH

Operator:

NEWFIELD PRODUCTION COMPANY

String type:

Surface

Project ID:

43-047-53656

Location:

UINTAH COUNTY

Design parameters:**Collapse**

Mud weight: 8.330 ppg
Design is based on evacuated pipe.

Minimum design factors:**Collapse:**

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No
Surface temperature: 74 °F
Bottom hole temperature: 109 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 100 ft

Cement top: 774 ft

Burst

Max anticipated surface pressure: 2,200 psi
Internal gradient: 0.120 psi/ft
Calculated BHP: 2,500 psi

Annular backup: 1.00 ppg

Tension:

8 Round STC: 1.80 (J)
8 Round LTC: 1.70 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.50 (B)

Tension is based on buoyed weight
Neutral point: 2,192 ft

Non-directional string.**Re subsequent strings:**

Next setting depth: 8,958 ft
Next mud weight: 11.500 ppg
Next setting BHP: 5,352 psi
Fracture mud wt: 19.250 ppg
Fracture depth: 2,500 ft
Injection pressure: 2,500 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost (\$)
1	2500	9.625	36.00	J-55	LT&C	2500	2500	8.796	20443
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (kips)	Tension Strength (kips)	Tension Design Factor
1	1082	2020	1.867	2370	3520	1.49	78.9	453	5.74 J

Prepared Helen Sadik-Macdonald
by: Div of Oil, Gas & Mining

Phone: 801 538-5357
FAX: 801-359-3940

Date: April 23, 2013
Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 2500 ft, a mud weight of 8.33 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Engineering responsibility for use of this design will be that of the purchaser.

Received: April 29, 2013

Well name:

43047536560000 Dart 4-14-3-2WH

Operator:

NEWFIELD PRODUCTION COMPANY

String type:

Intermediate

Project ID:

43-047-53656

Location:

UINTAH COUNTY

Design parameters:**Collapse**

Mud weight: 11.500 ppg
Internal fluid density: 1.200 ppg

Minimum design factors:**Collapse:**

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No
Surface temperature: 74 °F
Bottom hole temperature: 199 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 1,000 ft

Cement top: 4,740 ft

Burst

Max anticipated surface pressure: 3,381 psi
Internal gradient: 0.220 psi/ft
Calculated BHP 5,352 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
8 Round LTC: 1.80 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.60 (B)

Tension is based on air weight.

Neutral point: 7,427 ft

Directional Info - Build & Hold

Kick-off point 8466 ft
Departure at shoe 617 ft
Maximum dogleg: 11 °/100ft
Inclination at shoe: 89.93 °

Re subsequent strings:

Next setting depth: 8,765 ft
Next mud weight: 11.500 ppg
Next setting BHP: 5,236 psi
Fracture mud wt: 19.250 ppg
Fracture depth: 8,958 ft
Injection pressure: 8,958 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost (\$)
1	9348	7	29.00	P-110	Buttress	8958	9348	6.059	112967
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (kips)	Tension Strength (kips)	Tension Design Factor
1	4793	8530	1.780	5352	11220	2.10	259.8	929.4	3.58 B

Prepared Helen Sadik-Macdonald
by: Div of Oil, Gas & Mining

Phone: 801 538-5357
FAX: 801-359-3940

Date: April 23, 2013
Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 8958 ft, a mud weight of 11.5 ppg. An internal gradient of .062 psi/ft was used for collapse from TD. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Collapse strength is (biaxially) derated for doglegs in directional wells by multiplying the tensile stress by the cross section area to calculate a

Engineering responsibility for use of this design will be that of the purchaser.

Received: April 29, 2013

Well name:

43047536560000 Dart 4-14-3-2WH

Operator:

NEWFIELD PRODUCTION COMPANY

String type:

Production Liner

Project ID:

43-047-53656

Location:

UINTAH COUNTY

Design parameters:**Collapse**

Mud weight: 11.500 ppg

Design is based on evacuated pipe.

Minimum design factors:**Collapse:**

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No

Surface temperature: 74 °F

Bottom hole temperature: 197 °F

Temperature gradient: 1.40 °F/100ft

Minimum section length: 1,000 ft

Burst

Max anticipated surface

pressure: 3,308 psi

Internal gradient: 0.220 psi/ft

Calculated BHP 5,236 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)

8 Round LTC: 1.80 (J)

Buttress: 1.60 (J)

Premium: 1.50 (J)

Body yield: 1.60 (B)

Tension is based on air weight.

Neutral point: 8,818 ft

Liner top: 8,765 ft

Directional Info - Build & Hold

Kick-off point 8466 ft

Departure at shoe 4420 ft

Maximum dogleg: 11 °/100ft

Inclination at shoe: 92.93 °

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost (\$)
1	4533	4.5	13.50	P-110	Buttress	8765	13333	3.795	27195
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (kips)	Tension Strength (kips)	Tension Design Factor
1	5236	10680	2.040	5279	12410	2.35	.2	421.9	99.99 B

Prepared Helen Sadik-Macdonald
by: Div of Oil, Gas & MiningPhone: 801 538-5357
FAX: 801-359-3940Date: April 23, 2013
Salt Lake City, Utah**Remarks:**

For this liner string, the top is rounded to the nearest 100 ft. Collapse is based on a vertical depth of 8765 ft, a mud weight of 11.5 ppg. The Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Collapse strength is (biaxially) derated for doglegs in directional wells by multiplying the tensile stress by the cross section area to calculate a

Engineering responsibility for use of this design will be that of the purchaser.

Received: April 29, 2013

ON-SITE PREDRILL EVALUATION

Utah Division of Oil, Gas and Mining

Operator NEWFIELD PRODUCTION COMPANY
Well Name Dart 4-14-3-2WH
API Number 43047536560000 **APD No** 7723 **Field/Unit** UNDESIGNATED
Location: NWNW **Sec** 14 **Tw** 3.0S **Rng** 2.0W 250 FNL 201 FWL
1/4, 1/4
GPS Coord (UTM) 577796 4453563 **Surface Owner** Dart Homestead Ranch, Inc.

Participants

Bruce Dart - land owner; Corie Miller, Mandie Crozier - Newfiled; Jim Burns - Starpoint

Regional/Local Setting & Topography

The location is proposed on fallow grazing lands on the edge of the North Myton Bench. Drainages from the bench impact the site in two places. The area is rather barren of vegetation and the soils are clays. There are numerous eroded knolls and slight swales with an historic floodplain below. The location is one mile West of Highway 40 and 2 1/2 mile North of Myton just off Dart lane. The region is comprised of benches of differing levels and floodplains from the Duchesne River that has moved from its historic route. The soils are highly erodible and vegetation is sparse with the exception of the floodplains that are quite productive farmlands. Occasional buttes and numerous deep cut erosional features describe the region that is experiencing rapid growth in petroleum development.

Surface Use Plan

Current Surface Use

Grazing
Wildlife Habitat

New Road Miles

0.505

Well Pad

Width 300 **Length** 400

Src Const Material

Onsite

Surface Formation

UNTA

Ancillary Facilities

Waste Management Plan Adequate?

Environmental Parameters

Affected Floodplains and/or Wetlands N

Flora / Fauna

High desert shrubland ecosystem. Expected vegetation consists of black sagebrush, shadscale, Atriplex spp., mustard spp, rabbit brush, horsebrush, broom snakeweed, Opuntia spp and spring annuals.

Dominant vegetation;

Galletta, mat atriplex and broom snake weed

Wildlife;

Adjacent habitat contains forbs that may be suitable browse for deer, antelope, prairie dogs or rabbits. Wild turkeys have moved in and were encountered multiple times.

DWR did not respond with comments / issues

Received: April 30, 2013

Soil Type and Characteristics

Heavy light colored clay soils

Erosion Issues Y**Sedimentation Issues** Y**Site Stability Issues** N**Drainage Diversion Required?** Y**Berm Required?** Y**Erosion Sedimentation Control Required?** N**Paleo Survey Run?** N **Paleo Potential Observed?** N **Cultural Survey Run?** N **Cultural Resources?** N**Reserve Pit****Site-Specific Factors****Site Ranking****Distance to Groundwater (feet)** 75 to 100 10**Distance to Surface Water (feet)** 20**Dist. Nearest Municipal Well (ft)** 500 to 1320 10**Distance to Other Wells (feet)** >1320 0**Native Soil Type** Mod permeability 10**Fluid Type** Oil Base Mud Fluid 15**Drill Cuttings** Normal Rock 0**Annual Precipitation (inches)** 0**Affected Populations****Presence Nearby Utility Conduits** Present 15**Final Score** 80 1 Sensitivity Level**Characteristics / Requirements**

Operator intends to use an oil based drilling mud and is therefore required to use a closed loop system. If a reserve pit and freshwater is used, Pit to be dug to a depth of 8'. Because of the likely hood of disturbance to existing sandstone bedrock , pit underlayment is to be used to protect the liner from potential puncture. Pit should be fenced to prevent entry by deer, other wildlife and domestic animals. Pit to be closed within one year after drilling activities are complete.

Closed Loop Mud Required? Y **Liner Required?** Y **Liner Thickness** 16 **Pit Underlayment Required?** Y**Other Observations / Comments**Chris Jensen
Evaluator4/3/2013
Date / Time**Received: April 30, 2013**

Application for Permit to Drill Statement of Basis

Utah Division of Oil, Gas and Mining

APD No	API WellNo	Status	Well Type	Surf Owner	CBM
7723	43047536560000	LOCKED	OW	P	No
Operator	NEWFIELD PRODUCTION COMPANY		Surface Owner-APD	Dart Homestead Ranch, Inc.	
Well Name	Dart 4-14-3-2WH		Unit		
Field	UNDESIGNATED		Type of Work	DRILL	
Location	NWNW 14 3S 2W U 250 FNL (UTM) 577799E 4453556N		201 FWL GPS Coord		

Geologic Statement of Basis

Newfield proposes to set 60' of conductor and 2,500' of surface casing at this location. The base of the moderately saline water at this location is estimated to be at a depth of 2,250'. A search of Division of Water Rights records shows 10 water wells within a 10,000 foot radius of the center of Section 14. All wells are privately owned. Depth is listed as ranging from 30 to 300 feet. Average depth is approximately 100 feet. Water use is listed as irrigation, stock watering, and domestic. The surface formation at this site is the Uinta Formation. The Uinta Formation is made up of interbedded shales and sandstones. The sandstones are mostly lenticular and discontinuous and should not be a significant source of useable ground water. The proposed surface casing should adequately protect useable ground water in this area.

Brad Hill
APD Evaluator

4/16/2013
Date / Time

Surface Statement of Basis

Location is proposed in a good location although outside the spacing window typical of a horizontal well. Access road enters the pad from the east. The landowner was in attendance for the pre-site inspection.

The soil type and topography at present do combine to pose a small threat to erosion or sediment/ pollution transport in these regional climate conditions.

Usual construction standards of the Operator appear to be adequate for the proposed purpose as submitted. Operator has plans to use a closed loop system an oil based mud not indicated on plans.

I recognize no special flora or animal species or cultural resources on site that the proposed action may harm. The location was previously surveyed for cultural and paleontological resources as the operator saw fit. I have advised the operator take all measures necessary to comply with ESA and MBTA and that actions insure no disturbance to species that may have not been seen during onsite visit.

The location should be bermed to prevent fluids from entering or leaving the confines of the pad. Fencing around the reserve pit will be necessary to prevent wildlife and livestock from entering. A synthetic liner of 16 mils (minimum) should be utilized in the reserve pit. Measures (BMP's) shall be taken to protect steep slopes and topsoil pile from erosion, sedimentation and stability issues. A diversion is to be built sufficient to conduct overland or channel flow according to plans submitted

Received: April 30, 2013

Chris Jensen
Onsite Evaluator

4/3/2013
Date / Time

Conditions of Approval / Application for Permit to Drill

Category	Condition
Pits	A closed loop mud circulation system is required for this location.
Surface	Drainages adjacent to the proposed pad shall be diverted around the location.
Surface	The well site shall be bermed to prevent fluids from leaving the pad.
Surface	The reserve pit shall be fenced upon completion of drilling operations.
Surface	Measures (BMP's) shall be taken to protect steep slopes and topsoil pile from erosion, sedimentation and stability issues.

CONFIDENTIAL
Returned Unapproved

Received: April 30, 2013

**WORKSHEET
APPLICATION FOR PERMIT TO DRILL**

APD RECEIVED: 2/28/2013

API NO. ASSIGNED: 43047536560000

WELL NAME: Dart 4-14-3-2WH

OPERATOR: NEWFIELD PRODUCTION COMPANY (N2695)

PHONE NUMBER: 435 719-2018

CONTACT: Don Hamilton

PROPOSED LOCATION: NWNW 14 030S 020W

Permit Tech Review: ☒

SURFACE: 0250 FNL 0201 FWL

Engineering Review: ☒

BOTTOM: 0660 FSL 0660 FWL

Geology Review: ☒

COUNTY: UINTAH

LATITUDE: 40.22882

LONGITUDE: -110.08552

UTM SURF EASTINGS: 577799.00

NORTHINGS: 4453556.00

FIELD NAME: UNDESIGNATED

LEASE TYPE: 4 - Fee

LEASE NUMBER: Patented

PROPOSED PRODUCING FORMATION(S): GREEN RIVER

SURFACE OWNER: 4 - Fee

COALBED METHANE: NO

RECEIVED AND/OR REVIEWED:

LOCATION AND SITING:

☒ PLAT

☐ R649-2-3.

☒ Bond: STATE/FEE - B001834

Unit:

☐ Potash

☐ R649-3-2. General

☐ Oil Shale 190-5

☒ R649-3-3. Exception

☐ Oil Shale 190-3

☒ Drilling Unit

☐ Oil Shale 190-13

☒ Water Permit: 437478

Board Cause No: Cause 139-90

☐ RDCC Review:

Effective Date: 5/9/2012

☒ Fee Surface Agreement

Siting: 4 Prod LGRRV-WSTC Wells

☐ Intent to Commingle

☐ R649-3-11. Directional Drill

Commingle Approved

Comments: Presite Completed

Stipulations: 1 - Exception Location - bhill
5 - Statement of Basis - bhill
12 - Cement Volume (3) - hmadonald
25 - Surface Casing - hmadonald
27 - Other - bhill

Received: April 30, 2013



GARY R. HERBERT
Governor

GREGORY S. BELL
Lieutenant Governor

State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

May 02, 2013

NEWFIELD PRODUCTION
COMPANY
Rt 3 Box 3630
Myton, UT 84052

Re: Application for Permit to Drill - UINTAH County, Utah

Ladies and Gentlemen:

The Application for Permit to Drill (APD) for the Dart 4-14-3-2WH well, API 43047536560000 that was submitted February 28, 2013 is being returned unapproved. If you plan on drilling this well in the future, you must first submit a new application.

Should you have any questions regarding this matter, please call me at (801) 538-5312.

Sincerely,

Diana Mason
Environmental Scientist

Enclosure

cc: Bureau of Land Management, Vernal, Utah